# Experiment Proposal: AR\_2012\_No2

#### **Title**

## **Author/Spokesperson**

## **Test of duty factor measurement**

A. Reiter (1431)

#### **Summary & Aim**

- These tests are part of the R&D for PROJECT ABC
- Measurement of the duty factor of the slowly extracted SIS18 spill using 2 plastic scintillators at the end of the HTP beam line
- Requested beam time: 1 shift

### **Machine parameters**

Machine SIS18

Mode parasitic mode during B-exp at HTP

**Exp. area** HTP

Ion species Any

**Beam energy** Any

Spill length Any

Particle number Any

**Repetition rate** Any

Shifts 1

**Beam Time Period** Starting from March 2012

**Health & Safety** Not concerned

### **Experiment procedure**

The experiment uses the particle shower at the end of the beam line to monitor the duty factor of the spill indirectly. Therefore, the tests can be carried out parallel to any other experiment at HTP.

Follow approach described in NIM A339(1994) 425-428:

 $N_{A/B}$  = no. of counts of det. A/B during T

 $N_{AB}$  = no. of random coincidences during T

tau = coincidence resolving time

duty factor =  $(N_A \times N_B \times tau) / (N_{AB} \times T)$ 

**Experiment Setup** 

**Exp. area** HTP

**Description of** 2 plastic scintillators (GSI BLM type) connected to electronics in AP

container (coincidence logic). Then send signals to Ablass

**Duration of setup** Any

setup

**DAQ & Electronics** 2 detectors – discriminator – coincidence unit

**Software** Detector rates and the coincidence rate are monitored in a scaler

3 channels in Ablass system required

**Trigger** Standard Ablass (start cycle, end cycle)

**Experiment Preparation / Required support** 

Estimated amount of time, manpower and equipment

**Estimates or** Not required

simulations

**Mech.** Not required

Workshop

**Beam Line** 2 BLM-type scintillators next to beam line

Installation

**Electronics** Coincidence logic, Ablass readout

& DAQ

**Control System** Tobi/Harald HV for two detectors still available?

Integration

On-site tests

**Modification of** No

exp. area

**Dismantling** No special requirements

**Remarks & Comments**